Pelican Beach Resort Owners Association

Weekly Waterproofing Project Updates - Friday, September 30, 2022

Work began on Sept. 19. Since then, the contractor has been fixing multiple concrete spalls throughout the building. This work requires drilling out or cutting out of concrete all the way down to the rebar. Once they remove the damaged concrete, they refill it with new concrete. This is a noisy process as they use jackhammers to break the concrete. This work will be done throughout the duration of the project, including when they are working at or near the balconies.